

2005 New Well Inspection Schedule

Activity	Notification to EHS	Schedule *	Well Contractor Notes
Drill a new well	Yes	8:00 AM to 5:00 PM on regularly scheduled Mecklenburg County work days Date, Time , Place At least 1 Hour before you begin drilling	Permit must be on Site
Set Casing	No	There will not be a scheduled casing inspection. The EHS may conduct a casing inspection at anytime during well construction.	For sites where casing is set after regularly scheduled inspection hours, the well contractor shall not install the pump or finish the wellhead until the day following the next regularly scheduled Mecklenburg County work day after the casing is set.
Grout Inspection	Yes	8:00 AM to 4:00 PM on regularly scheduled Mecklenburg County work days	Well contractor schedules a time for grout inspection with the EHS at least four (4) hours prior to the requested inspection time. **
Final Inspection	Yes	8:00 AM to 3:00 PM on regularly scheduled Mecklenburg County work days	The Well contractor shall Notify the EHS that the well is complete and the system is free of chlorine residual.

EHS = Environmental Health Specialist

*Scheduling should be confirmed by the EHS handling the permit.

**If the EHS is not on site within 30 minutes after the scheduled time, the well contractor may proceed to grout the well in absence of the EHS. If Well contractor is unable to begin grouting within 30 minutes after the scheduled time or the arrival of the EHS, in cases where the EHS has arrived after the scheduled time, the grouting inspection shall be rescheduled a minimum of two hours later during normal inspection times.